

ITEM	MILESTONES / LINE ITEMS	Units	QTY	UNIT PRICE	TOTAL COSTING
1	SECTION 1: PRELIMINARY AND GENERAL				
1.1	FIXED CHARGE AND VALUE RELATED ITEMS				
1.1.1	Compliance with the Health & Safety Specifications	Sum	1		
1.1.2	Compliance with the Environmental Management Plan	Sum	1		
TOTAL: SECTION 1					
SECTION 2: ELECTRICAL WORKS					
2	SECTION 2 ELECTRICAL SCOPE				
2.1	Assess and fault-find MCC panel of Unit 4 Aerators (45kW to 110kW) (Bio 1 to Bio 4) and produce written assessment report of faults and compliance deviations.	No.	25		
2.2	Repair faults and non-compliance issues as per findings of report called for in item 2.1	Sum	1	R250 000,00	R250 000,00
2.3	Percentage mark up on item 2.2 above	%			
2.4	Replace damaged and faulty cable for Unit 4 Bio 3 Aerator 5 (size and length to verify on side briefing) – supply and install splice kit and cable c/w ferrules and other consumables	m	100		
2.5	Rewire screw pump MCC panels and supply missing and damaged components	No.	4		
2.6	Rewire Unit 4 ET screens MCC panels and supply missing and damaged components.	No.	2		
2.7	Rewire Unit 4 ET pumps MCC panels and supply missing and damaged components.	No.	2		
2.8	Test aerator motors and provide written report.	No.	25		
2.9	Test field cables of the aerator motors and provide written report	No.	25		
2.10	Repair faults and non-compliance issues as per findings of report called for in item 2.9	Sum	1	R60 000,00	R60 000,00
2.11	Test and inspect the MCC panels of operational Unit 4 bioreactor screw pumps and provide written report.	No.	4		

2.12	Repair faults and non-compliance issues as per findings of report called for in item 2.11	Sum	1	R80 000,00	R80 000,00
2.13	Percentage mark up on item 2.17 above	%			
2.14	Supply and deliver fuse: TCP100M200	No.	12		
2.15	Supply and deliver soft starter: PSTX72-600-70	No.	2		
2.16	Supply and deliver ABB switch fuse, front operated, 3-pole, middle, 250A (complete) suitable for TCP100M200 fuse link	No.	1		
TOTAL SECTION 2					
SUB-TOTAL (SECTION 1 + 2)					
15 % Vat					
GRAND TOTAL					

Signature of person authorized to sign this tender (BOQ Sign-off):

Name: _____ **Signature:** _____

Date: _____