



MEMBER	No OF	BARS PER MEMB	DIA.	LENGTH	TOTAL NUM- BER	MARK	S C	B E N D I N G				
								A	B	C	D	E/r
	1	2	Y20	7800	2	12ab	55	550	1500	3870	1500	(550)
		2	Y20	7350	2	12ac	55	550	1500	3420	1500	(550)
		2	Y20	6800	2	12ad	55	550	1500	2900	1500	(550)
		2	Y20	6150	2	12ae	55	550	1500	2220	1500	(550)
		2	Y20	5100	2	12af	55	550	1500	1170	1500	(550)
		2	Y16	9200	2	13a	38	800	7650	(800)		
		2	Y16	9150	2	13b	38	800	7630	(800)		
		2	Y16	9100	2	13c	38	800	7580	(800)		
		2	Y16	9050	2	13d	38	800	7520	(800)		
		2	Y16	8950	2	13e	38	800	7430	(800)		
		2	Y16	8750	2	13f	38	800	7230	(800)		
		2	Y16	8700	2	13g	38	800	7190	(800)		
		2	Y16	8550	2	13h	38	800	7040	(800)		
		2	Y16	8400	2	13i	38	800	6850	(800)		
		2	Y16	8150	2	13j	38	800	6640	(800)		
		2	Y16	7900	2	13k	38	800	6390	(800)		
		2	Y16	7650	2	13l	38	800	6110	(800)		
		2	Y16	7300	2	13m	38	800	5790	(800)		
		2	Y16	6950	2	13n	38	800	5420	(800)		
		2	Y16	6500	2	13o	38	800	4990	(800)		
		2	Y16	6000	2	13p	38	800	4480	(800)		
		2	Y16	5400	2	13q	38	800	3870	(800)		
		2	Y16	4600	2	13r	38	800	3080	(800)		
		2	Y16	3450	2	13s	38	800	1940	(800)		
		30	Y16	9100	30	14	65	9100				3850
		186	Y16	2750	186	10	37	200	(2600)			
		261	R10	500	261	15	85	150	300	50	(50)	
	8	10	12	16	20	25	32	40	TOT	Date	2023/09/14	
R		80							80	Det. by	AM 	
Y			1692	164					1856	Ref Dwg	C01486-SR01	
TOT		80	1692	164					1936	Job No	J147	
			JW14406 - LINBRO PARK TOWER (3.0ML WATER TOWER): PILE CAPS AND BEAMS REINFORCEMENT BENDING SCHEDULE							Revision		0
										Schedule No		C01486-SR01-BS03