


MEMBER	No OF	BARS PER MEMB	DIA.	LENGTH	TOTAL NUM- BER	MARK	S C	B E N D I N G				
								A	B	C	D	E/r
	4	3	Y20	6900	12	17a	20	(6900)				
		3	Y20	6800	12	17b	20	(6800)				
		3	Y20	6750	12	17c	20	(6750)				
		3	Y20	6600	12	17d	20	(6600)				
		3	Y20	6550	12	17e	20	(6550)				
		3	Y10	6500	12	17f	20	(6500)				
		3	Y20	6400	12	17g	20	(6400)				
		3	Y20	6350	12	17h	20	(6350)				
		3	Y20	6350	12	17i	20	(6350)				
		3	Y20	6300	12	17j	20	(6300)				
		3	Y20	6200	12	17k	20	(6200)				
		3	Y20	6150	12	17l	20	(6150)				
		3	Y20	6100	12	17m	20	(6100)				
		3	Y20	6000	12	17n	20	(6000)				
		3	Y20	5650	12	18a	20	(5650)				
		3	Y20	5600	12	18b	20	(5600)				
		3	Y20	5550	12	18c	20	(5550)				
		3	Y20	5450	12	18d	20	(5450)				
		3	Y20	5400	12	18e	20	(5400)				
		3	Y20	5350	12	18f	20	(5350)				
		3	Y10	5300	12	18g	20	(5300)				
		3	Y20	5200	12	18h	20	(5200)				
		3	Y20	5150	12	18i	20	(5150)				
		3	Y20	5100	12	18j	20	(5100)				
		3	Y20	5000	12	18k	20	(5000)				
		3	Y20	4950	12	18l	20	(4950)				
		3	Y20	4900	12	18m	20	(4900)				
		3	Y20	4800	12	18n	20	(4800)				
		3	Y20	4750	12	18o	20	(4750)				
		3	Y20	4700	12	18p	20	(4700)				
		3	Y20	4600	12	18q	20	(4600)				
		3	Y20	4550	12	18r	20	(4550)				
		3	Y20	4500	12	18s	20	(4500)				
		3	Y20	4400	12	18t	20	(4400)				
		3	Y20	4350	12	18u	20	(4350)				
		3	Y20	4300	12	18v	20	(4300)				
		3	Y10	4250	12	18w	20	(4250)				
		3	Y20	4150	12	18x	20	(4150)				
		3	Y20	4100	12	18y	20	(4100)				
		3	Y20	4050	12	18z	20	(4050)				
		3	Y20	3950	12	19a	20	(3950)				
		3	Y20	3900	12	19b	20	(3900)				
		3	Y20	3850	12	19c	20	(3850)				
		1	Y20	10400	4	20a	65	10400				6474
		1	Y20	10200	4	20b	65	10200				6349
		1	Y20	10000	4	20c	65	10000				6224
		1	Y20	9800	4	20d	65	9800				6099
		1	Y20	9600	4	20e	65	9600				5974
		1	Y20	9400	4	20f	65	9400				5849
		1	Y20	9200	4	20g	65	9200				5724
		1	Y20	9000	4	20h	65	9000				5599
	8	10	12	16	20	25	32	40	TOT	Date	2023/09/14	
R										Det. by	SC <i>Shinbanga</i>	
Y		119			7031				7149	Ref Dwg	C01486-SR05	
TOT		119			7031				7149	Job No	J147	
				JW14406 - LINBRO PARK TOWER (3.0ML WATER TOWER): FLOOR SLAB REINFORCEMENT BENDING SCHEDULE						Revision		0
										Schedule No		C01486-SR05-BS04