


MEMBER	No OF	BARS PER MEMB	DIA.	LENGTH	TOTAL NUM- BER	MARK	S C	B E N D I N G				
								A	B	C	D	E/r
	4	1	Y20	8800	4	20i	65	8800				5474
		1	Y10	8600	4	20j	65	8600				5349
		1	Y20	8450	4	20k	65	8450				5224
		1	Y20	8250	4	20l	65	8250				5099
		1	Y20	8050	4	20m	65	8050				4974
		1	Y20	7850	4	20n	65	7850				4849
		1	Y20	7650	4	20o	65	7650				4724
		1	Y20	7450	4	20p	65	7450				4599
		1	Y20	7250	4	20q	65	7250				4474
		1	Y20	7050	4	20r	65	7050				4349
		1	Y20	6850	4	20s	65	6850				4224
		1	Y20	6650	4	20t	65	6650				4099
		1	Y20	6450	4	20u	65	6450				3974
		1	Y20	6250	4	20v	65	6250				3849
		1	Y20	6050	4	20w	65	6050				3724
		1	Y20	5850	4	20x	65	5850				3599
		1	Y20	5700	4	20y	65	5700				3474
		1	Y10	5500	4	20z	65	5500				3349
		1	Y20	5300	4	21a	65	5300				3224
		1	Y20	5100	4	21b	65	5100				3099
		1	Y20	4900	4	21c	65	4900				2974
		1	Y20	4050	4	22a	65	4050				2450
		1	Y20	3900	4	22b	65	3900				2325
		1	Y20	3700	4	22c	65	3700				2200
		1	Y20	3500	4	22d	65	3500				2075
		1	Y20	3300	4	22e	65	3300				1950
		1	Y20	3100	4	22f	65	3100				1825
		1	Y20	2900	4	22g	65	2900				1700
		1	Y20	2700	4	22h	65	2700				1575
	8	10	12	16	20	25	32	40	TOT	Date	2023/09/14	
R										Det. by	SC <i>Shinhangga</i>	
Y		35			1549				1584	Ref Dwg	C01486-SR05	
TOT		35			1549				1584	Job No	J147	
				JW14406 - LINBRO PARK TOWER (3.0ML WATER TOWER): FLOOR SLAB REINFORCEMENT BENDING SCHEDULE						Revision		0
										Schedule No		C01486-SR05-BS05