


MEMBER	No OF	BARS PER MEMB	DIA.	LENGTH	TOTAL NUM- BER	MARK	S C	B E N D I N G				
								A	B	C	D	E/r
250 THICK ROOF SLAB	4	282	Y12	6400	1128	01	20	(6400)				
		72	Y12	5250	288	02	20	(5250)				
		72	Y12	3950	288	03	20	(3950)				
		16	Y12	4300	64	04	20	(4300)				
		16	Y12	4300	64	05	20	(4300)				
		6	Y12	7250	24	06a	20	(7250)				
		6	Y12	7200	24	06b	20	(7200)				
		6	Y12	7100	24	06c	20	(7100)				
		6	Y12	7050	24	06d	20	(7050)				
		6	Y12	6950	24	06e	20	(6950)				
		6	Y12	6850	24	06f	20	(6850)				
		6	Y12	6800	24	06g	20	(6800)				
		6	Y12	6700	24	06h	20	(6700)				
		6	Y12	6650	24	06i	20	(6650)				
		6	Y12	6550	24	06j	20	(6550)				
		6	Y12	6500	24	06k	20	(6500)				
		6	Y12	6400	24	06l	20	(6400)				
		6	Y12	6350	24	06m	20	(6350)				
		6	Y12	6250	24	06n	20	(6250)				
		6	Y12	6150	24	06o	20	(6150)				
		6	Y12	6100	24	06p	20	(6100)				
		6	Y12	6000	24	06q	20	(6000)				
		6	Y12	5950	24	06r	20	(5950)				
		6	Y12	5850	24	06s	20	(5850)				
		6	Y12	5800	24	06t	20	(5800)				
		6	Y12	5700	24	06u	20	(5700)				
		6	Y12	5600	24	06v	20	(5600)				
		6	Y12	5500	24	06w	20	(5500)				
		6	Y12	5450	24	06x	20	(5450)				
		6	Y12	5400	24	06y	20	(5400)				
		6	Y12	5300	24	06z	20	(5300)				
		6	Y12	5250	24	07a	20	(5250)				
		6	Y12	5150	24	07b	20	(5150)				
		6	Y12	5050	24	07c	20	(5050)				
		6	Y12	5000	24	07d	20	(5000)				
		6	Y12	4900	24	07e	20	(4900)				
		6	Y12	4850	24	07f	20	(4850)				
		6	Y12	4750	24	07g	20	(4750)				
		6	Y12	4700	24	07h	20	(4700)				
		6	Y12	4600	24	07i	20	(4600)				
		6	Y12	4500	24	07j	20	(4500)				
		6	Y12	4450	24	07k	20	(4450)				
		6	Y12	4350	24	07i	20	(4350)				
		6	Y12	4300	24	07m	20	(4300)				
		6	Y12	4200	24	07n	20	(4200)				
		6	Y12	4150	24	07o	20	(4150)				
		6	Y12	4050	24	07p	20	(4050)				
		6	Y12	3950	24	07q	20	(3950)				
		6	Y12	3900	24	07r	20	(3900)				
		6	Y12	3800	24	07s	20	(3800)				
		6	Y12	3750	24	07t	20	(3750)				
	8	10	12	16	20	25	32	40	TOT	Date	2023/09/14	
R										Det. by	SC <i>Shinhangga</i>	
Y			14642						14642	Ref Dwg	C01486-SR08	
TOT			14642						14642	Job No	J147	
				JW14406 - LINBRO PARK TOWER (3.0ML WATER TOWER): ROOF SLAB REINFORCEMENT BENDING SCHEDULE						Revision		0
										Schedule No		C01486-SR08-BS01