


MEMBER	No OF	BARS PER MEMB	DIA.	LENGTH	TOTAL NUM- BER	MARK	S C	B E N D I N G				
								A	B	C	D	E/r
	4	6	Y12	3650	24	07u	20	(3650)				
		6	Y12	3600	24	07v	20	(3600)				
		6	Y12	3500	24	07w	20	(3500)				
		6	Y12	3400	24	07x	20	(3400)				
		6	Y12	3350	24	07y	20	(3350)				
		6	Y12	3250	24	07z	20	(3250)				
		6	Y12	3200	24	08a	20	(3200)				
		6	Y12	3100	24	08b	20	(3100)				
		6	Y12	3050	24	08c	20	(3050)				
		6	Y12	2950	24	08d	20	(2950)				
		2	Y12	7400	8	08e	65	7400				4300
		2	Y12	7150	8	08f	65	7150				4150
		2	Y12	6850	8	08g	65	6850				4000
		2	Y12	6650	8	08h	65	6650				3850
		2	Y12	6450	8	08i	65	6450				3700
		2	Y12	6200	8	08j	65	6200				3550
		2	Y12	5950	8	08k	65	5950				3400
		2	Y12	5750	8	08i	65	5750				3250
		2	Y12	5500	8	08m	65	5500				3100
		2	Y12	5250	8	08n	65	5250				2950
		2	Y12	5000	8	08o	65	5000				2800
		2	Y12	4800	8	08p	65	4800				2650
		2	Y12	4550	8	08q	65	4550				2500
		2	Y12	4300	8	08r	65	4300				2350
		2	Y12	4100	8	08s	65	4100				2200
		2	Y12	3850	8	08t	65	3850				2050
		2	Y12	3600	8	08u	65	3600				1900
		2	Y12	3350	8	08v	65	3350				1750
		4	Y12	3200	16	08w	65	3200				1600
		6	Y20	10750	24	09	20	(10750)				
		6	Y16	10650	24	10	20	(10650)				
		104	Y10	1200	416	11	60	225	300			
		130	Y10	850	520	12	83	200	120	250	(250)	
	8	10	12	16	20	25	32	40	TOT	Date	2023/09/14	
R										Det. by	SC <i>Shinhang</i>	
Y		580	1436	403	636				3056	Ref Dwg	C01486-SR08	
TOT		580	1436	403	636				3056	Job No	J147	
				JW14406 - LINBRO PARK TOWER (3.0ML WATER TOWER): ROOF SLAB REINFORCEMENT BENDING SCHEDULE						Revision		0
										Schedule No		C01486-SR08-BS01