



- NOTES: REINFORCED CONCRETE**
1. THE APPLICABLE STANDARD SPECIFICATION IS SANS 12005 - 1982 WHICH SHOULD BE READ IN CONJUNCTION WITH THE VARIATIONS AND ADDITIONS CONTAINED IN THE PROJECT SPECIFICATION FOR CONCRETE (STRUCTURAL).
 2. CONCRETE COVER TO REINFORCEMENT AND CONCRETE STRENGTH TO BE AS INDICATED BELOW. COVER IS GIVEN TO THE NEAREST FACE. MINIMUM BAR COVER TO BE MAXIMUM OF BAR DIAMETER AND AS SHOWN BELOW. SPECIFIED COVER TO BE MAINTAINED USING CEMENT MORTAR COVER BLOCKS OR APPROVED PLASTIC SPACERS.
 3. ALL AGGREGATE TO BE 19mm UNLESS OTHERWISE SPECIFIED.
 4. CONCRETE DESIGN MIXES TO BE SUBMITTED TO ENGINEER FOR COMMENTS PRIOR TO CONSTRUCTION.
 5. CUBE TESTS TO BE CARRIED OUT ON SITE AND LOGGED WITH POSITION AND DATE. CUBES TO BE TAKEN FOR EACH TYPE OF ELEMENT, AT LEAST ONE SET DAILY AND AT LEAST ONE SET EVERY 50m.
 6. REINFORCEMENT TO BE IN ACCORDANCE WITH SANS 920 AND SHALL BE BENT IN ACCORDANCE WITH SANS 92.
 7. ALL CAST IN ITEMS SHALL BE FREE OF OIL, GREASE, DIRT OR ANY OTHER MATERIAL WHICH MAY IMPAIR THE BOND WITH THE CONCRETE. CONTRACTOR TO REFER TO ARCHITECT SPECIALIST DRAWINGS FOR DETAILS POSITIONS OF OPENINGS, SLEEVES, CONDUITS, ETC. FOR STORMWATER, SEWERAGE AND OTHER SERVICES.
 8. FOUNDATIONS HAVE BEEN DESIGNED FOR AN ALLOWABLE GROUND BEARING CAPACITY OF 1000 kPa.
 9. ALL FOUNDATION EXCAVATIONS TO BE INSPECTED BY THE GEOTECHNICAL ENGINEER PRIOR TO CONCRETING.
 10. REMOVAL OF FORMWORK TO BE IN ACCORDANCE WITH THE PROJECT SPECIFICATION. IT IS THE CONTRACTOR'S RESPONSIBILITY FOR BACK-PROPPING ON MULTI-STORY SLAB CONSTRUCTION.
 11. ALL EXPOSED CORNERS TO BE CHAMFERED 25x25 0.U.N.

SOP - SETTING OUT POINT	
NAME	COORDINATE
SOP 1	Y = 99379.526 X = 2875664.847
SOP 2	Y = 99381.840 X = 2875639.502
SOP 3	Y = 99384.113 X = 2875614.666
SOP 4	Y = 99386.388 X = 2875589.710
SOP 5	Y = 99388.660 X = 2875564.813
SOP 6	Y = 99390.932 X = 2875539.917
SOP 7	Y = 99393.247 X = 2875514.572

CONSULTANTS DWG NO	
13247-02/S/008/A	
DRAWING No.	
JW14455	A
PROJECT No.	DRAWING No.
A0	1 OF 4
ORIGINAL PAGE SIZE	
FILE No.	

themba Confidence • Trust • INFRASTRUCTURE CONSULTING Tel: 0861themba (843633) email: info@themba-africa.com	DESIGNED	KB	10/02/2021
	DRAWN	LD	30/09/2024
	CHECKED	WM	30/09/2024
	APPROVED BY:	SIGNATURE	DATE
CLIENT JOHANNESBURG WATER TURBINE HACC 62 NTEMI PICISO STREET NEW TOWN	ECOSA REG. No.		
	CHECKED BY:	SIGNATURE	DATE
		SIGNATURE	DATE
		SIGNATURE	DATE



TURBINE HACC
62 NTEMI PICISO STREET
NEWTOWN
TEL: (011) 688-1400
FAX: (011) 688-1521

Joburg
DIEPSLOOT SEWAGE AQUEDUCT
BRIDGE 3
GENERAL ARRANGEMENT
1 OF 2

SURVEY INFORMATION		APPROVAL BY JW DEPOT		SCALE	AMENDMENTS	
PROJECT SURVEYOR:		CHECKED		AS SHOWN	REV:	DATE:
DATE:		APPROVED BY:		A	ISSUED FOR TENDER	30/09/2024
		SIGNATURE	DATE			
CCTV INFORMATION		APPROVAL BY JW PLANNING				
CCTV COMPANY:		CHECKED				
DATE:		APPROVED BY:				
		SIGNATURE	DATE			