



- NOTES: REINFORCED CONCRETE**
1. THE APPLICABLE STANDARD SPECIFICATION IS SANS 12006 - 1982 WHICH SHOULD BE READ IN CONJUNCTION WITH THE VARIATIONS AND ADDITIONS CONTAINED IN THEMBA PROJECT SPECIFICATION FOR CONCRETE (STRUCTURAL).
 2. CONCRETE COVER TO REINFORCEMENT AND CONCRETE STRENGTH TO BE AS INDICATED BELOW. COVER IS GIVEN TO THE NEAREST FACE. MINIMUM BAR COVER TO BE MAXIMUM OF BAR DIAMETER AND AS SHOWN BELOW. SPECIFIED COVER TO BE MAINTAINED USING CEMENT MORTAR COVER BLOCKS OR APPROVED PLASTIC SPACERS.
 3. ALL AGGREGATE TO BE 10mm UNLESS OTHERWISE SPECIFIED.
 4. CONCRETE DESIGN MIXES TO BE SUBMITTED TO ENGINEER FOR COMMENTS PRIOR TO CONSTRUCTION.
 5. CUBE TESTS TO BE CARRIED OUT ON SITE AND LOGGED WITH POSITION AND DATE. CUBES TO BE TAKEN FOR EACH TYPE OF ELEMENT, AT LEAST ONE SET DAILY AND AT LEAST ONE SET EVERY 50m³.
 6. REINFORCEMENT TO BE IN ACCORDANCE WITH SANS 920 AND SHALL BE BENT IN ACCORDANCE WITH SANS 920.
 7. ALL CAST IN ITEMS SHALL BE FREE OF OIL, GREASE, DIRT OR ANY OTHER MATERIAL WHICH MAY IMPAIR THE BOND WITH THE CONCRETE. CONTRACTOR TO REFER TO ARCHITECT (SPECIALIST DRAWINGS FOR DETAILS) POSITIONS OF OPENINGS, SLEEVES, CONDUITS, ETC. FOR STORMWATER, SEWERAGE AND OTHER SERVICES.
 8. FOUNDATIONS HAVE BEEN DESIGNED FOR AN ALLOWABLE GROUND BEARING CAPACITY OF 1000 kPa.
 9. ALL FOUNDATION EXCAVATIONS TO BE INSPECTED BY THE GEOTECHNICAL ENGINEER PRIOR TO CONCRETING.
 10. REMOVAL OF FORMWORK TO BE IN ACCORDANCE WITH THE PROJECT SPECIFICATION. IT IS THE CONTRACTOR'S RESPONSIBILITY FOR BACK-PROPPING ON MULTI-STORY SLAB CONSTRUCTION.
 11. ALL EXPOSED CORNERS TO BE CHAMFERED 25x25 O.U.N.

themba
Confidence • Trust •

INFRASTRUCTURE CONSULTING

Tel: 0861themba (843622)
email: info@themba-africa.com

CLIENT
JOHANNESBURG WATER
TURBINE HACC
62 NTEMI PICISO STREET
NEW TOWN

DESIGNED	KB	10/02/2021
DRAWN	WM	30/09/2024
CHECKED	LD	30/09/2024
APPROVED BY:	SIGNATURE	DATE
ECSA REG. No.		
CHECKED BY:	SIGNATURE	DATE



TURBINE HACC
62 NTEMI PICISO STREET
NEWTOWN

TEL: (011) 688-1400
FAX: (011) 688-1521

Joburg

DIEPSLOOT SEWAGE AQUEDUCT
BRIDGE 2

DECK 3 REBAR DETAIL

SURVEY INFORMATION		APPROVAL BY JW DEPOT		SCALE	AMENDMENTS	
PROJECT SURVEYOR:		CHECKED		AS SHOWN	REV:	DESCRIPTION
DATE:		APPROVED BY:		A	ISSUED FOR TENDER	30/09/24
CCTV INFORMATION		SIGNATURE	DATE			
CCTV COMPANY:		APPROVAL BY JW PLANNING				
DATE:		CHECKED				
		APPROVED BY:				
		SIGNATURE	DATE			

CONSULTANTS DWG NO

13247-02/S/R020/A

DRAWING No.

JW14455

PROJECT No.

A0

SHEET

3

OF

4

ORIGINAL PAGE SIZE

FILE No.

DRAWING No.

A

REV.

30/09/24