


ANOTHER  
JOHANNESBURG WATER  
SERVICE  
DELIVERY PROJECT  
HELPDESK (011)375-5555



A world class African City



PROJECT DETAILS:  
CONTRACT NO.: JW14471

DESCRIPTION: SEALING OF THE  
LEAKING CONCRETE WATER SUMP

CONSULTANT:  
KEON TECHNO JV  
TEL: 011 045 2532

CONTRACTOR:  
.....  
TEL.....

CLIENT  
JOHANNESBURG WATER-  
PROJECT MANAGEMENT UNIT  
TEL: 011 688 1400

FONT : 70mm  
780  
FONT : 60mm  
SPACING : 60mm  
FONT : 70mm  
540  
FONT : 50mm  
SPACING : 50mm  
540  
FONT : 70mm  
540  
FONT : 50mm  
SPACING : 50mm

Engineer:  
**KEON**  
CONSULTING ENGINEERS  
**TECHNO**  
DESIGNS  
Civil Structural & Transport Engineers

TECHNO DESIGNS  
ENGINEERING  
34 Dang Street Glen Austin  
Midrand  
TELEPHONE (011) 045 2532  
CELL (072) 301 1811  
EMAIL: engineer@technodesigns.co.za  
WEBSITE: www.technodesigns.co.za

KEON CONSULTING  
ENGINEERS  
5th Avenue Office Park,  
4th Floor, Avenue Newton  
Port Elizabeth  
TELEPHONE: 07 413630189  
WEBSITE: www.keon.co.za

Client:  
**Johannesburg Water**  
Turbine Hall,  
65 Meiri Ploos Street,  
Newtown, Johannesburg

THESE NOTES SERVE AS AN ADDENDUM TO THE SPECIFICATION IN THE BILL OF QUANTITIES (BOQ). IN THOSE CASES WHERE THE BOQ SPECIFICATIONS DIFFER FROM THESE NOTES, THESE NOTES SHALL TAKE PRECEDENCE ON ORIGINAL

Engineer:  
T.Chikwata Pr Eng (20140009)  
M. Mulumba  
T. Maplumo  
T. Chikwata

Drawn By: M. Mulumba  
Designed By: T. Maplumo  
Checked By: T. Chikwata

Signature: \_\_\_\_\_  
Date: November 2024

Signature: \_\_\_\_\_  
Date: November 2024

Signature: \_\_\_\_\_  
Date: November 2024

**CONCRETE NOTES:**

1.0 SETTING OUT AND GENERAL  
1.1 THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ARCHITECTS' DRAWINGS.  
1.2 ALL DIMENSIONS AND HEIGHTS ARE TO BE CHECKED ON SITE BEFORE WORK IS PUT IN HAND.  
1.3 REPORT DISCREPANCIES TO ARCHITECT OR ENGINEER.  
1.4 THIS DRAWING MUST NOT BE USED TO SCALE OFF. USE ONLY WRITTEN DIMENSIONS. CONTACT THE ENGINEER OR ARCHITECT WHERE CLARITY IS SOUGHT.  
1.5 FOR SETTING OUT DATA, SETTING OUT POINTS AND DATUM LEVELS REFER TO SURVEY INFORMATION AND ARCHITECTS' DRAWINGS.

2.2 NO FOUNDATIONS ARE TO BE CAST IN FILL MATERIAL. A 50mm THICK LAYER OF 10MPa / 19mm BLINDING CONCRETE IS TO BE CAST UNDER ALL REINFORCED BASES, REINFORCED STRIP FOOTINGS AND GROUND BEAMS.  
2.3 ANY OVER EXCAVATIONS ARE TO BE MADE GOOD WITH 10MPa / 19mm CONCRETE AT THE CONTRACTOR'S EXPENSE.  
2.4 BACKFILLING OVER COLUMN BASES SHALL BE DONE WITH AN APPROVED MATERIAL, COMPACTED IN LAYERS IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.  
2.5 ALLOWABLE BEARING PRESSURE UNDER:  
CONCRETE BASES = 150kPa  
STRIP FOOTINGS = 100kPa

3.0 CONCRETE  
3.1 CONCRETE CHARACTERISTIC 28 DAY STRENGTH:  
BASES: 25MPa / 19mm  
STRIP FOOTINGS: 25MPa / 19mm  
SURFACE BEDS: 30MPa / 19mm  
SUSPENDED SLABS & BEAMS: 30MPa / 19mm  
COLUMNS: 30MPa / 19mm

3.2 CONCRETE MIX DESIGNS FOR ALL GRADES OF CONCRETE TO BE GIVEN TO ENGINEER FOR PERUSAL AND COMMENT. CONCRETE MIX DESIGNS FOR SURFACE BEDS TO HAVE MINIMUM BLEED CHARACTERISTICS.  
3.3 ALL CONCRETE TO BE ADEQUATELY CURED BY KEEPING SURFACES CONTINUOUSLY DAMP FOR AT LEAST 5 DAYS AFTER CASTING.

3.4 ALL CONCRETE TO BE CONSTRUCTED TO THE S.A.N.S 1200G PERMISSIBLE DEVIATION DEGREE OF ACCURACY CLASS II UNLESS SPECIFIED OTHERWISE.  
3.5 CONCRETE CUBE TEST RESULTS TO BE SUBMITTED TIMELY TO ENGINEER FOR PERUSAL, RECORDS, COMMENT AND APPROVAL.

4.0 REINFORCEMENT  
4.1 CHARACTERISTIC STRENGTH: 250N/mm<sup>2</sup>  
4.2 MILD STEEL: 450N/mm<sup>2</sup>  
4.3 ALL REINFORCEMENT TO BE CHECKED AND APPROVED BY ENGINEER BEFORE ANY CONCRETE IS CAST. 48 HOURS WRITTEN NOTICE TO BE GIVEN TO ENGINEER BEFORE TIME OF INSPECTION.  
4.4 LAP LENGTH TO REINFORCING TO BE MINIMUM 50 x SMALLER BAR DIAMETER, UNLESS OTHERWISE NOTED.  
4.5 MESH REINFORCEMENT REFERENCE 245 TO BE PLACED IN SLAB (TOP) MINIMUM LAPS = 300mm UNLESS OTHERWISE NOTED.  
4.6 THE CONTRACTOR MUST TAKE PARTICULAR CARE TO ENSURE THAT THE SPECIFIED COVER TO ALL REINFORCEMENT HAS BEEN ATTAINED THROUGHOUT BEFORE THE ENGINEER IS CALLED TO SITE FOR INSPECTION OF THE REINFORCEMENT.

4.7 SUSPENDED BEAMS: 30mm  
CONTRACTOR IS TO CONDUCT HIS OWN INSPECTION OF REINFORCEMENT BEFORE CALLING THE ENGINEER FOR INSPECTION.  
5.0 FORMWORK AND PROPPING  
5.1 STRIPPING TIMES FOR:  
COLUMN AND WALL SHUTTERING: 1.5 DAYS  
BEAM SHUTTERING: 7 DAYS IN HOT WEATHER, 12 DAYS IN COLD WEATHER, 4 DAYS IN HOT WEATHER, 7 DAYS IN COLD WEATHER.  
5.2 PROPPING TIMES FOR:  
SLABS AND BEAMS: 14 DAYS IN HOT WEATHER, 21 DAYS IN COLD WEATHER, 21 DAYS  
CANTILEVER SLABS AND BEAMS: (SUBJECT TO CUBE TEST RESULTS BEING SUBMITTED TIMELY TO ENGINEER FOR APPROVAL)  
NO DE-PROPPING OF SUSPENDED ELEMENTS UNTIL INSTRUCTED BY ENGINEER.  
5.3 CONCRETE FINISHES: UNLESS NOTED OTHERWISE  
COLUMNS AND WALLS: OFF SHUTTER  
BEAMS AND SLAB SOFFIT: OFF SHUTTER  
TOP OF SUSPENDED SLABS: STEEL FLOAT  
SURFACE BEDS: POWER FLOAT  
5.4 SIDES OF GROUND BEAMS TO BE SHUTTERED.

Refer To Drawing No:

Key Plan:

Project:  
JW14471-SEALING OF THE LEAKING  
CONCRETE WATER SUMP

Description:  
NAME BOARD

Issued For:  
TENDER

Size: A1  
Scale: As Shown  
Sheet No: 1 OF 1  
Original Date: November 2024

Project No: JW14471  
Drawing No: STRUCT-04  
Revision: 0