



Engineer: KEON CONSULTING ENGINEERS TECHNO DESIGNS Civil Structural & Transport Engineers	Client: Johannesburg Water Turbine Hall, 65 Menni Pilosa Street, Newtown, Johannesburg	<p>THESE NOTES SERVE AS AN ADDENDUM TO THE SPECIFICATION IN THE BILL OF QUANTITIES (BOQ). IN THOSE CASES WHERE THE BOQ SPECIFICATIONS DIFFER FROM THESE NOTES, THESE NOTES SHALL TAKE PRECEDENCE ON ORIGINAL.</p> <p>0 5 10 15 20 25 30 40 50MM</p> <p>Engineer: T.Chikwata Pr Eng (20140009) <i>T.Chikwata</i></p> <p>Drawn By: M. Mulumba Designed By: T. Mapfumo Checked By: T. Chikwata</p> <p>Signature: <i>T. Chikwata</i> Date: October 2024</p>	<p>CONCRETE NOTES:</p> <p>1.0 SETTING OUT AND GENERAL</p> <p>1.1 THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ARCHITECT'S DRAWINGS.</p> <p>1.2 ALL DIMENSIONS AND HEIGHTS ARE TO BE CHECKED ON SITE BEFORE WORK IS PUT IN HAND.</p> <p>1.3 REPORT DISCREPANCIES TO ARCHITECT OR ENGINEER.</p> <p>1.4 THIS DRAWING MUST NOT BE USED TO SCALE OFF. USE ONLY WRITTEN DIMENSIONS. CONTACT THE ENGINEER OR ARCHITECT WHERE CLARITY IS SOUGHT.</p> <p>1.5 FOR SETTING OUT DATA, SETTING OUT POINTS AND DATUM LEVELS REFER TO SURVEY INFORMATION AND ARCHITECT'S DRAWINGS.</p> <p>1.6 STRUCTURAL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH THE PROJECT SPECIFICATION AND THE RELEVANT S.A.N.S SPECIFICATIONS. ALL CONCRETE WORK IS TO BE DONE IN ACCORDANCE WITH S.A.N.S 12000 AND EARTHWORKS IN ACCORDANCE WITH S.A.N.S 12000.</p> <p>1.8 CONSULT RELEVANT ARCHITECT'S, MECHANICAL, ELECTRICAL & PLUMBING DRAWINGS AND DETAILS AS RELEVANT FOR DRAINAGE, STORMWATER OUTLETS, RWOPS AND HOLES AND SLEEVES FOR THESE SERVICES. NO HOLES ARE TO BE CORED WITHOUT ENGINEER'S WRITTEN APPROVAL.</p> <p>2.0 FOUNDATIONS</p> <p>2.1 ALL FOUNDATION EXCAVATIONS TO BE INSPECTED AND APPROVED IN WRITING BY THE ENGINEER BEFORE CONCRETE IS CAST.</p> <p>2.2 NO FOUNDATIONS ARE TO BE CAST IN FILL MATERIAL. A 50mm THICK LAYER OF 10MPa / 19mm BLINDING CONCRETE IS TO BE CAST UNDER ALL REINFORCED BASES, REINFORCED STRIP FOOTINGS AND GROUND BEAMS.</p> <p>2.3 ANY OVER EXCAVATIONS ARE TO BE MADE GOOD WITH 10MPa / 19mm CONCRETE AT THE CONTRACTOR'S EXPENSE.</p> <p>2.4 BACKFILLING OVER COLUMN BASES SHALL BE DONE WITH AN APPROVED MATERIAL, COMPACTED IN LAYERS IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.</p> <p>2.5 ALLOWABLE BEARING PRESSURE UNDER: CONCRETE BASES = 150kPa STRIP FOOTINGS = 100kPa</p> <p>3.0 CONCRETE</p> <p>3.1 CONCRETE CHARACTERISTIC 28 DAY STRENGTH: BASES: 25MPa / 19mm STRIP FOOTINGS: 30MPa / 19mm SURFACE BEDS: 30MPa / 19mm SUSPENDED SLABS & BEAMS: 30MPa / 19mm COLUMNS: 30MPa / 19mm</p> <p>3.2 CONCRETE MIX DESIGNS FOR ALL GRADES OF CONCRETE TO BE GIVEN TO ENGINEER FOR PERUSAL AND COMMENT. CONCRETE MIX DESIGNS FOR SURFACE BEDS TO HAVE MINIMUM BLEED CHARACTERISTICS.</p> <p>3.3 ALL CONCRETE TO BE ADEQUATELY CURED BY KEEPING SURFACES CONTINUOUSLY DAMP FOR AT LEAST 5 DAYS AFTER CASTING.</p> <p>3.4 ALL CONCRETE TO BE CONSTRUCTED TO THE S.A.N.S 12000 PERMISSIBLE DEVIATION DEGREE OF ACCURACY CLASS II UNLESS SPECIFIED OTHERWISE.</p> <p>3.5 CONCRETE CUBE TEST RESULTS TO BE SUBMITTED TIMELY TO ENGINEER FOR PERUSAL, RECORDS, COMMENT AND APPROVAL.</p> <p>4.0 REINFORCEMENT</p> <p>4.1 CHARACTERISTIC STRENGTH: MILD STEEL: 250N/mm² HIGH YIELD STEEL: 450N/mm²</p> <p>4.2 ALL REINFORCEMENT TO BE CHECKED AND APPROVED BY ENGINEER BEFORE ANY CONCRETE IS CAST. 48 HOURS WRITTEN NOTICE TO BE GIVEN TO ENGINEER BEFORE TIME OF INSPECTION.</p> <p>4.3 LAP LENGTH TO REINFORCING TO BE MINIMUM 50 x SMALLER BAR DIAMETER, UNLESS OTHERWISE NOTED.</p> <p>4.4 MESH REINFORCEMENT REFERENCE 245 TO BE PLACED IN SLAB (TOP) MINIMUM LAPS = 300mm UNLESS OTHERWISE NOTED.</p> <p>4.5 THE CONTRACTOR MUST TAKE PARTICULAR CARE TO ENSURE THAT THE SPECIFIED COVER TO ALL REINFORCEMENT HAS BEEN ATTAINED THROUGHOUT BEFORE THE ENGINEER IS CALLED TO SITE FOR INSPECTION OF THE REINFORCEMENT.</p> <p>4.6 COVER TO REINFORCEMENT: BASES: 50mm COLUMNS AND WALLS: 50mm SUSPENDED SLABS: 30mm</p> <p>4.7 SUSPENDED BEAMS: 30mm</p> <p>4.8 CONTRACTOR IS TO CONDUCT HIS OWN INSPECTION OF REINFORCEMENT BEFORE CALLING THE ENGINEER FOR INSPECTION.</p> <p>5.0 FORMWORK AND PROPPING</p> <p>5.1 STRIPPING TIMES FOR: COLUMN AND WALL SHUTTERING: 15 DAYS BEAM SHUTTERING: 7 DAYS IN HOT WEATHER, 12 DAYS IN COLD WEATHER, 4 DAYS IN HOT WEATHER, 7 DAYS IN COLD WEATHER.</p> <p>5.2 PROPPING TIMES FOR: SLABS AND BEAMS: 14 DAYS IN HOT WEATHER, 21 DAYS IN COLD WEATHER</p> <p>5.3 CANTILEVER SLABS AND BEAMS: (SUBJECT TO CUBE TEST RESULTS BEING SUBMITTED TIMELY TO ENGINEER FOR APPROVAL) NO DE-PROPPING OF SUSPENDED ELEMENTS UNTIL INSTRUCTED BY ENGINEER.</p> <p>5.4 CONCRETE FINISHES: UNLESS NOTED OTHERWISE COLUMNS AND WALLS: OFF SHUTTER BEAMS AND SLAB SOFFIT: OFF SHUTTER TOP OF SUSPENDED SLABS: STEEL FLOAT SURFACE BEDS: POWER FLOAT SIDES OF GROUND BEAMS TO BE SHUTTERED.</p>	<p>Refer to Drawing No:</p> <p>Key Plan:</p>	<p>Project: JW14468- FEMALE ABLUTION STAND BY FACILITY</p> <p>Description: CONCRETE FOUNDATION LAYOUT&DETAILS</p> <p>Issued For: TENDER</p> <table border="1"><thead><tr><th>Size</th><th>Scale</th><th>Sheet No.</th><th>Original Date</th></tr></thead><tbody><tr><td>A1</td><td>As Shown</td><td>1 OF 1</td><td>October 2024</td></tr></tbody></table> <table border="1"><thead><tr><th>Project No.</th><th>Drawing No.</th><th>Revision</th></tr></thead><tbody><tr><td>JW14468</td><td>STRUCT-14</td><td>0</td></tr></tbody></table>	Size	Scale	Sheet No.	Original Date	A1	As Shown	1 OF 1	October 2024	Project No.	Drawing No.	Revision	JW14468	STRUCT-14	0
Size	Scale	Sheet No.	Original Date																
A1	As Shown	1 OF 1	October 2024																
Project No.	Drawing No.	Revision																	
JW14468	STRUCT-14	0																	